



SPD-RSS-5512-16'-5.5" DIA .125"

Round Straight Galvanized Steel Pole



Tenon Post Top




The **SC114** Tenon is to be used for all floodlight cluster assemblies

Physical Data


Pole Height: 16'
 Pole Diameter: 5.5"
 Thickness: 0.125"
 Weight: 141 lbs
 EPA: 0.982m² - 10.57ft²

Pole Mount Install Notes

Option A




Option B




Anchor Bolt

D x L x C x T
 $\frac{3}{4}$ x 18 x 4 x 6



Mounting Base



Die-Cast Base Cover




Not to scale template:

This drawing is being furnished for reference dimensions only and cannot be used as a template to set anchor bolts. Since it is "not to scale" Ligman accepts no responsibility for its intended use. Refer to site plans and specification before installing any anchor bolts.

• Contact Ligman Lighting USA for bolt template prior to pouring anchor bolts.

Wind Load Map - For Regions with Winds Greater than 100MPH, Contact Ligman USA

Maximum EPA is based on the luminaire weight shown. Increased luminaire weight may reduce the maximum EPA. If weight is exceeded, or if other design life or code is required, please contact Ligman USA



SPD-RSS-5512-16'-5.5" DIA .125" Round Straight Galvanized Steel Pole

PROJECT		DATE	
---------	--	------	--

QUANTITY		TYPE		NOTE	
----------	--	------	--	------	--

ORDERING EXAMPLE || SPD - RSS - 5512 - 16' - 5.5" - DIA .125" - TOP CAP - 02 - Options

--	--	--	--	--	--

FINISH COLOR	ADDITIONAL OPTIONS - CONSULT FACTORY FOR PRICING
--------------	--

01 - BLACK RAL 9011



A20781 - Single Banner Arm

02 - DARK GREY RAL 7043



A20881 - Double Banner Arm

03 - WHITE RAL 9003



GFCI - GFCI Box

04 - METALLIC SILVER RAL 9006



1LS - 1.5mm [1/16"] Leveling Shim [Enter Quantity]

05 - MATTE SILVER RAL 9006



3LS - 3mm [1/8"] Leveling Shim [Enter Quantity]


06 - LIGMAN BRONZE




07 - CUSTOM RAL




LS
Leveling Shim



A20781
Single Banner Arm



A20881
Double Banner Arm



GFCI
GFCI Box

Banner arms are designed with a safety break-away at the clamp with an internal safety wire that prevents the arm from falling to the ground. It is important to calculate the additional EPA loading on the pole based on the size and quantity of banners.

Adding banners will affect the EPA of the pole and should be taken into consideration before installing.

Incorrect pole loading of any type voids pole warranty.

More Custom Finishes Available Upon Request


Consult factory for pricing and lead times

MicroPRIM FINISHES

- SW01 - OAK FINISH
- SW02 - WALNUT FINISH
- SW03 - PINE FINISH
- DF - DOUGLAS FIR FINISH
- CW - CHERRY WOOD FINISH
- NW - NATIONAL WALNUT FINISH
- SU01 - CONCRETE FINISH
- SU02 - SOFTSCAPE FINISH
- SU03 - STONE FINISH
- SU04 - CORTEN FINISH
- CSM - Custom Image/Pattern

MicroPRIM FINISHES

- MP - MAPLE FINISH
- MHG - MAHOGANY FINISH
- BH - BEECH FINISH
- CN - CHESTNUT FINISH
- WMBL - WHITE MARBLE FINISH
- MBL - MARBLE FINISH
- GRNT - GRANITE FINISH
- BGD - BRUSHED GOLD FINISH
- BBRZ - BRUSHED BRONZE FINISH
- CAMO - CAMOUFLAGE FINISH
- MP01 - MicroPRIM RAL 9011 Black (Glossy)
- MP02 - MicroPRIM RAL 7043 Dark Grey (Glossy)
- MP03 - MicroPRIM RAL 9003 White (Glossy)
- MP04 - MicroPRIM RAL 9006 Metallic Silver (Glossy)
- MP05 - MicroPRIM RAL 9006 Matte Silver (Matte/Textured)
- MP06 - MicroPRIM Ligman Bronze (Glossy)
- MP07 - MicroPRIM Custom Color (Glossy)




MicroPRIM Finish



Anchor Bolt Installation for Poles


What's Included Per Pole




- x 4**
- x 8**
- x 8**

A single anchor bolt template is provided per pole size to be used for the poles on the project.

Anchor bolt template may be round or square dependant upon which pole is being used.



1 Use anchor bolt template to set anchor bolts into concrete as per civil engineering instructions.




2 Ensure that the concrete is plumb using a level. Failing to do this will result in pole being uneven or tilted.

Ligman does not provide foundation details. A local engineer that is familiar with the site soil conditions should provide this information.

NOTE:
Ligman does not recommend using leveling Shims for pole installations.

Leveling shims can be provided, contact Ligman for more information.



Leveling Shim Example

Preferred Pole Installation

Note : Bolt cover stops flush with the pole base plate

2"

4.65"


Non-Shrink Grout to be provided by contractor after leveling pole

A level concrete base is poured and finished flush. This provides a uniform load displacement pad for the forces created by wind and luminaire weight

Failing to do this voids pole warranty
Foundation and Design by Others

In rare instances where leveling bolts have to be used, it is important that a flush concrete surface is created to mount the pole base plate.
NOTE: When using leveling bolts, bolt projection should be 3.5"

Using Leveling Bolts Option A




After establishing a level platform the space between the original concrete surface and the pole base should be filled with concrete and finished flush.

This provides a uniform load displacement pad for the forces created by wind and luminaire weight

Foundation and Design by Others

Using Leveling Bolts Option B



After establishing a level platform the space between the original concrete surface and the pole base should be filled with concrete and finished flush.

This provides a uniform load displacement pad for the forces created by wind and luminaire weight